

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50373/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/16/2021-22, Date: 15-03-2022

Name of Work: Construction of Culverts and Improvements to drain Bharatnagar cross road in Ward No.06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SURESH UPPALAPATI ()	
				In Figures	In Words
1	124.8	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	85.0	Rupees Eighty Five Only
2	21	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	4900.0	Rupees Four Thousand Nine Hundred Only
3	2.88	Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	TONNE	80000.0	Rupees Eighty Thousand Only
4	43.7	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	7000.0	Rupees Seven Thousand Only
5	90.9	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge.	Sqm	1258.89	Rupees One Thousand Two Hundred Fifty Eight and Eighty Nine Paise Only
6	28.8	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	4500.0	Rupees Four Thousand Five Hundred Only

U. Suresh
Signature of the Contractor

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 560075
12/04